MYSORE DIVISION.

ADVERTISEMENT.

The 4th November 1891.

Tenders are hereby invited for restoring Inam-Umattur Tank, Registered No. 27, Chamrajnagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1894.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's Office between the hours of 11 A. M. and 4 P. M., daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 27th November 1891.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 100 as earnest money.

6. Within 8 days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on [illegible]ed tenders will be returned to applicants in due course.

Description of Work.		Quantity.	Rate tendered.	Remarks.
Bund—				
Earthwork	C. Yd.	33,832		
Puddling	"	45		
Old stone work	"	3,059		
New stone work	"	6,877		
Clearing jungle	L. S.	.		
Grade stone	No.	81		
Register number stone	"	1		
B. M. stones	"	2		
Gauge stones	"	1		
Sluices—				
Examining and repairing both the sluices ..	L. S.	..		
Waste Weir—				
Earthwork	C. Yds.	609		
Old stone work	"	173		
New stone work	"	152		
Clearing site	L. S.	..		
Surki concrete	C. Ft.	1,266		
Brick in surki mortar	"	2,936		
Chunam plastering	Sqr.	14·22		
Slab stones	S. Ft.	351		
Sundry—				
Earthwork		55		

V. H. KARVE,
Executive Engineer.